

### Utilities Coordinating Committee of the Lower Cape Fear Serving New Hanover, Brunswick, and Pender Counties July 18, 2017

Meeting held at Wilmington Airport

Time begins: 9:04am Time end: 10:00am

Members' Introductions – 19 members attended

Call meeting to order – Joyce Cantrell

Glenn Carroll - Chairperson
Joyce Cantrell- Secretary

This month's challenge - prepare for donations for UCC Fall BBQ and coat drive

NC 811 – Howard Corey
Statewide Locate Requests / Transmission numbers
County Ticket Volume
County Ticket Distribution
Summer Heat video
Events, Meetings, Holidays
Mock Line Strike
How can an 811 liaison help you today?
www.ncucc.org

### City of Wilmington presentation - Skipper Funderburg

ROW Program
Keeping Pace
Who gets the call??
Permitting References
Street Cut Policy – 2011
Caution for Traffic Control
Brick Streets

Commitments from the City

Handouts: Street Cut Policy and Official Brick & Stone Streets Policy Map

Their policies can be found on their website www.wilmingtonnc.gov

### **Discussions**

Design Tickets are considered new tickets but has a 10 working day notice. The locator can locate the facilities, provide maps of the facilities, and/or show the facilities personally. Objective is to promote design tickets to plan for proposed work to eliminate potential conflicts.

Fall BBQ is scheduled October 17<sup>th</sup> at Hugh McRae Park. Asked Brett to reserve shelter #6 for us. Cater is Mussers Chicken and BBQ. The total bill is estimated to be \$1200. Asked companies to think about participating in the funding and donations. If your company needs an invoice to give to accounting, let Joyce know.

Give back to the community at the Fall BBQ with a coat drive. Suggestion was made by Brett to add flannel shirts with the coats. The clothing will be donated to worthy cause. Brett also suggested to have corn hole game at the BBQ event.

### **Projects**

Piedmont Natural Gas

Riverlights and Brunswick Forest phases

City of Wilmington – Transport Bond Project Sidewalk work at and around Delaney Dr Central College Trail project

New Hanover County

Middle Sound Green bike trail

New Hanover Regional Medical Hospital

Skyway Bridge from the new employees parking deck over S. 17<sup>th</sup> Street to the Hospital parking lot Used by employee staff only

### **Adjourn Meeting**


Next month's meeting August 15<sup>th</sup> at City of Wilmington EOC Conference Room (209 Coleman Dr, Wilmington) at 9:00 a.m.

### **UCC Meeting**

### Sign in Sheet -7/18/17

(Please print)

Name	Organization	Email Address
Jayre Moderals	PNG	joye. m. dette piedmentige
Mark Fowler	TOC13	Mark Fould Q Cura In G 13 each
Michael Mote	TOCB	mike. mote@(arolinabeach.org
-N. Ja Balan	PNG.	
Howard Core,	NCGI	howardenession
Roger Dun	PNG	roger, dunn@pedmaiting.com
William Caryle	PNG	William. Cayle opiedmentay. con
Nick Drees	NC DOT	nkdiess Byahoo.com
Angel Hamners	NCBOT, District 3	akhammers@nedot.gov
Jee Murphy	Mastec	Soe. Mujhya Maste. com
MARVIN Foster	FLM	mfosteal flykm.com
Joyce Cantrell	PNG	joyce cantrellapredmontagecom
Bret Russell	LOW	bret resellour lang torre gov
SKApper Funderbury	COW	skipper. Fundedung e"
Philip Shuster.	COW	Philip. shuster & city of wilmington
DS MEDEURS	PNG	
Bill Dykes	Spectrum	text bill. dykes@ Charter.com
Hunter marealy	PRG-	hmartaly proconsulting net
TODO KING	McKim & CREED	TKING @ MOLIM CREED, COM



- NOTES:
- 1. CONTRACTOR SHALL ENSURE BOTTOM OF TRENCH IS SUITABLE FOR INSTALLATION AND DOES NOT REQUIRE FOUNDATION CONDITIONING STONE.
- 2. FILL SHALL BE SUITABLE MATERIAL THAT IS FREE FROM HEAVY CLAY, GUMBOS, DEBRIS, ORGANICS AND LITTLE TO NO EXCESSIVE MOISTURE.
- 3. SELECT BACKFILL MAY BE SUBSTITUTED OR REQUIRED BY CITY TO ACHIEVE COMPACTION, (I.E. #57, ABC, CRUSHED LIMESTONE, CLEAN SAND, FLOWABLE FILL, ETC).
- 4. SOIL SHALL BE INSTALLED IN 6"-8" LIFTS AND COMPACTED BY A MECHANIZED TAMPER (I.E JUMPING JACK), HOWEVER, VIBRATORY ROLLERS > 18" WIDTH MAY BE USED FOR LARGER EXCAVATIONS. THE PLATE TAMP METHOD SHALL NOT BE USED.
- 5. ALL APPROVED CASTINGS SHALL BE SET FLUSH TO GRADE AND SUPPORTED IF APPLICABLE.
- 6. COMPACT MATERIALS TO MINIMUM % DENSITY SHOWN IN DIAGRAM AS DETERMINED BY THE STANDARD PROCTOR METHOD ASTM D-698-A FOR SOILS; AND ASTM D-698-C FOR ABC STONE; AND BY NUCLEAR GAUGE OR CORE SAMPLE FOR ASPHALT.
- 7. CUTBACKS OF ASPHALT SHALL BE PREPARED ON EDGE OF EXCAVATION OVER TOP OF UNDISTURBED SOIL.

	STANDARD DETAIL	TV/city of
DATE: MAY, 2013	PAVEMENT REPAIRS-	WILMINGTON NORTH CAROLINA
DRAWN BY JSR	UTILITY CUTS	CITY OF WILMINGTON
CHECKED BY D.E.C., P.E.	OTILITI COIS	ENGINEERING OFFICE 212 OPERATIONS CENTER DRIVE
SCALE NOT TO SCALE		WILMINGTON N.C. 28412 (910) 341-7807 SD 1-05





### **City of Wilmington Street Cut Policy**

"No person shall make any excavations in any public right-of-way without first making application and paying applicable fees..." (Ch II, Article V, Section 11-74)

#### I. Introduction

To ensure that City streets are functional and to provide reasonable regulation of excavations this policy is authorized by the Wilmington Code, Chapter 11 (Article V. Excavations and Use of Rights-of-Way). Prior to the excavation of any asphalt, brick or concrete street an Applicant shall:

- 1. Submit a Right-of-Way (ROW) permit application, supporting documents and fee(s) to the City Engineering ROW Department.
  - 2 weeks to review 'non-standard' or project related requests.
- 2. Receive permit, coordinate and commence work.

Approval of ROW permits for utility cuts will be based on the construction needs and the type of street(s) (major thoroughfare, arterial, collector, minor, etc), which shall dictate the size of excavation, amount of pavement restoration, curb work, sidewalk work, available work hours, traffic control, possible detours or public notifications, and quality control, i.e. inspections.

Applicant and Permittee shall be responsible to coordinate all non-city utility issues and for quality of work performed by excavators and pavers to ensure all City Policies, Technical Standard and Details are met. All restoration is provided with an 18-month warranty by applicant. (Section 11-96).

The City Engineer has the right to deny a permit or issue a stop work order for non-compliance.

#### II. Permits & Fees

ROW permits and fees are managed through City Engineering, ROW Department (341-5899). Supporting documents may require a scope of work, traffic control plan, etc as necessary. Both the ROW permit and Open Cut fees are due at the time of application.

ROW Permit fee - \$10. Open Cut fee - \$325.

Online applications can be made at: www.wilmingtonnc.gov. (link to Departments / Public Services)

Additional coordination may be required with City Street Department (341-5888).

Additional coordination may be required with City Traffic Engineering Department (341-7888).

Copies of permits must be maintained on sight at all times (Section 11-81). Failure to make available upon request may result in the stoppage of work (Section 11-100).

#### III. Non City Owned Streets

A City permit would not apply to NCDOT ROW, private roads or parking lots.

### IV. Utility Locates and Excavation

All excavators shall call (811) to utilize the North Carolina One-Call Center (NCOCC) for locate requests, marking, positive response, etc. prior to excavation and with proper request times (i.e 48-hours in advance). Excavators shall exercise appropriate caution to avoid damage and ensure safety. All excavators fall under North Carolina General Statute 87 and City of Wilmington Code Chapter 11, Articles I and V for adherence to excavation rules and penalties. (Section 11-95).

### V. Emergency Excavations

In case of an emergency excavation, applications for permits and fees shall be made no later than 24 hours following excavation. An emergency situation is considered a sudden loss or failure of service or an accident to a utility facility where the impacts are deemed an imminent danger to the public health and safety. In the case of an emergency the utility facility may be accessed for necessary repairs and site control.

#### VI. Traffic Control & Public Notification

All excavations affecting motorists and pedestrians shall require a proper traffic control plan submitted with each ROW application. The plan shall be based on the type of street(s) and the amount of traffic using the Manual of Uniform Traffic Control Devices (MUTCD Part 6 –Temporary Traffic Control) for guidance. Depending on the impact to traffic, businesses or residents, public notification plans (signs, advertisements, flyers, etc) may be necessary and submitted as part of the permit. (Section 11-94).

#### VII. Trench and Street Repair

Reference shall be made to City of Wilmington Technical Standards and Details for all repairs. See SD 1-05 for street repair. Excavators shall factor soil contents and soil moisture when backfilling a trench with the intent to avoid the creation of voids, soil bridging or settlement.

- Backfill shall be suitable material that is free from heavy clay, gumbos, debris, organics and little to no excessive moisture.
- Select backfill may be substituted or required by City to achieve compaction, (i.e. #57, ABC, crushed limestone, clean sand, flowable fill, etc).
- 8-inch of aggregate base course (ABC) material shall be used on City streets.
- Backfill and base materials shall be compacted in 12" maximum lifts.
- Soil shall be compacted by a mechanized tamper (i.e jumping jack) for most excavations, however, vibratory rollers > 18" width may be used for larger excavations. Under no circumstances shall the plate tamp method be used.
- All approved castings shall be set flush to grade and supported if applicable.
- ABC and subbase compacted to 98% and backfill and embedment compacted to 90% of the maximum dry density as determined by the modified AASHTO Method T-99.
- 1-foot cutbacks of existing asphalt shall be made on undisturbed soil. Clean square cuts shall be applied with tack to all asphalt joints.
- Superpave 9.5A or B asphalt shall be installed in lifts to match the existing pavement thickness in or 2" minimum. Minimum asphalt density is 90% of maximum specific gravity.

#### VIII. Pavement Restoration

Where excavations impact the pavement, the applicant shall provide the dimensions on the permit. Applicant shall utilize Figure1, to develop the limits of pavement restoration. All pavement restoration cuts shall tend to be linear and perpendicular while avoiding the wheel path. Where an applicant requires multiple cuts in a block or section of street, the City reserves the right to require full lane or full width restoration. (Section 11-96). For instance, if 35% of the asphalt or consecutive cuts are made within a block (typical 500') or lane the City may require full lane or full width restoration. Additionally, no pavement restoration shall be left less than 5' from the edge of curb or roadway. Where utility excavation occurs on a newly resurfaced area or a substantial road section (i.e high volume), additional paving and/or milling may be required. Extended milling shall extend a minimum of 10' either side of the excavation. Milling shall be no less than 1-inch in depth. An applicant may also be asked to extend pavement in collaboration with the City Streets department or others to assist with efforts to maintain streets in good working condition.

#### IX. Restoration for all other City Facilities

Where excavations impact other City facilities such as stormwater piping or boxes, driveways, curbing, sidewalks, signs, traffic loops, lighting, landscaping, etc the contractor shall reference all applicable City of Wilmington Technical Standards and Details to restore these facilities. Directional drilling methods may be used to cross under a driveway, curb or sidewalk; however, there will be no tunneling or jetting for this purpose. Concrete provided for restoration shall be from a drum mix.

### X. Quality Control and Inspections

The City requires strict adherence to standard details and permit requirements. Observation and Quality Control testing may be performed and/or required for compaction efforts, densities, stone or asphalt thickness, materials delivered, job mix formula, trucking tickets, etc. At no cost to the City, these observation and testing efforts may be required, with any testing results submitted to the City within 2 business days. These tests may include observation, compaction, stone densities, asphalt cores, asphalt densities, etc. Failure to adequately meet minimal standards or test requirements shall result in re-excavation and re-work of the trench or restoration to the satisfaction of the City.

### XI. Temporary Repair

Where construction activities require a trench to be backfilled or covered for any reason, including restoring traffic, resuming construction, or awaiting asphalt restoration, the contractor shall safely maintain the trench and all traffic control until the following temporary pavement repairs are made on a suitable base in a safe manner:

Less than 24-hours -6" compacted ABC stone -2" hot mix or cold patch asphalt -2" minimum hot mix asphalt

Steel plates may be used up to 30 days with prior approval from the City. Cold patch materials are not considered a permanent pavement application and thus are only acceptable for a period of 30 days. Depending on the type of street and weather conditions the City reserves the right to determine the type of temporary asphalt repairs required at that time.

### XII. Final Asphalt and Striping Restoration

Upon completion of the utility work the contractor restore pavement and striping in a timely manner to minimize impacts to the travelling public, typically 3-5 business days. Appropriate tack shall be used and Superpave 9.5A or B asphalt shall be applied in lifts to match existing thickness or a minimum of 2-inches with a minimum density of 90%. Any alternate material shall first be approved by City Engineering prior to placement. Under no circumstances shall the contractor attempt to skim patch on top of existing asphalt.

Removed traffic markings or striping shall be restored within 3 days using original thermo-plastic or paint materials.

#### XIII. Brick Street Restoration

Excavators shall become familiar with City requirements to secure the bricks for reuse in a careful manner and deliver to the City Operations center by contacting the Streets department. The excavation of bricks shall generally be performed by hand with pry bar tools to avoid damage, stacked on wooden pallets and wrapped for delivery. Typically, for the final layer, excavators install 12-inches of compacted ABC (98% density) and then notify City of completion for subsequent installation of bricks.

#### XIV. Concrete Street Restoration


Upon completion of the trench the utility or contractor shall be allowed to pour concrete. The common standard shall be 4000 psi concrete. Any alternate material shall be first approved by the City Engineer prior to placement. New concrete shall be applied to the same thickness as existing conditions or a minimum of 6-inches.

#### XV. Worksite Safety and Access

Any Permittee conducting repairs, excavation or utility work shall take reasonable actions and precautions to ensure that such work does not endanger people or property, nor interfere with the free and proper use of public streets, alleys, sidewalks, bridges, etc. nor hinder with the operation of any other utilities, etc. (Section 11-91).


#### XVI. Warranty

All excavations and street repairs shall be guaranteed against failure for a period of 18 months after completion of asphalt restoration. The warranty period shall start the first of the month following completion. Example: a repair completed on the 20<sup>th</sup> of June shall be warranted from July 1st until December 31<sup>st</sup> the following year. A failure is defined as settlement greater than 1/8 -inch in depth as determined by the DOT straight edge method, pulled joints, cracking of the patch; etc. Upon discovery of failures from inspections, the City may contact Applicant of such failures to make repairs as needed. (Section 11-96).



- 1) THE LIMITS OF PAVEMENT RESTORATION SHALL DEPEND ON LOCATION OF UTILITY TRENCHING, AS WELL AS SURROUNDING PAVEMENT CONDITION AND MARKINGS. PAVEMENT REPAIRS SHALL BE SUBJECT TO THE CITY STREET CUT POLICY, DETAIL SD 1-05 AND SHALL MEET OR EXCEED CURRENT STANDARDS.
- 2) 12-INCH CUTBACKS REQUIRED BEYOND ALL VOIDS AND WHERE TRENCH WALLS ARE NOT BENCHED OR INSPECTED OR CONSIDERED COMPROMISED.
- 3) PAVEMENTS REPAIRS SHALL GENERALLY AVOID EDGES ALONG A WHEEL PATH AND THEREFORE BE EXTENDED TO THE MIDDLE OR NEXT CLOSEST LANE.
- 4) WHERE THERE ARE MULTIPLE CUTS OR DISTURBED AREAS GREATER THAN 35% ON A SINGLE LANE OR ENTIRE ROAD SURFACE, THE CITY MAY REQUIRE FULL WIDTH REPAIR.
- 5) THE CITY OF WILMINGTON WILL ASSESS THE LIMITS OF NECESSARY PAVEMENT RESTORATION BASED ON THESE GUIDELINES AND MAY ASSIST MARKING AREAS ( I.E. SPRAY PAINT) ONCE THE ASPHALT HAS BEEN BROOM CLEANED AND MADE VISIBLE FOR INSPECTION.

	STREET CUT POLICY - FIGURE 1	TV/CITY OF
DATE: APRIL, 2011	PAVEMENT RESTORATION	WILMINGTON
DRAWN BY JSR	GUIDELINES	NORTH CAROLINA CITY OF WILMINGTON
CHECKED BY B.R., P.E.	GOIDELINES	ENGINEERING OFFICE    414 CHESTNUT STREET
SCALE NOT TO SCALE		WILMINGTON N.C. 28401 (910) 341-7807 FIGURE 1





## Statewide Ticket and Transmission Data

**June:** 2017 / 2016 Comparison

### **Tickets**

2017: 170,404

2016: 175,428

Difference: -2.9%

### **Transmissions**

2017: 971,633

2016: 949,373

Difference: 2.3%





## Statewide Ticket and Transmission Data

Year-to-Date: 2017 / 2016 Comparison

### **Tickets**

2017: 969,119

2016: 933,728

Difference: 3.8%

### **Transmissions**

2017: 5,499,795

2016: 4,992,894

Difference: 10.2%







June: 2017 Stats Compared with 2016

			Type 7	Γicket		
New Hanover	3 HR	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	32	47	2616	40	982	3717
2017	33	41	2775	71	1292	4212
+/- Var	3.1%	-12.8%	6.1%	77.5%	31.6%	13.3%
			Avg L	ocates pei	r Day	191



June: 2017 Stats Compared with 2016

			Type 7	Γicket		
Brunswick	$3~\mathrm{HR}$	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	11	17	2030	26	583	2667
2017	55	36	3187	42	1983	5303
+/- Var	400.0%	111.8%	57.0%	61.5%	240.1%	98.8%
			Avg L	ocates per	Day	241



June: 2017 Stats Compared with 2016

	Type Ticket					
Pender	3 HR	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	5	14	907	11	163	1100
2017	24	6	1033	77	570	1710
+/- Var	380.0%	-57.1%	13.9%	600.0%	249.7%	55.5%
			Avg I	∡ocates pei	c Day	78



Year-to-Date: 2017 Stats Compared with 2016

	Type Ticket					
New Hanover	3 HR	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	182	245	14536	332	5353	20648
2017	188	245	15439	360	6984	23216
+/- Var	3.3%	0.0%	6.2%	8.4%	30.5%	12.4%
			Avg I	Locates per	r Day	184



Year-to-Date: 2017 Stats Compared with 2016

			Type T	'icket		
Brunswick	3 HR	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	100	150	11605	199	4298	16352
2017	186	250	16817	300	7993	25546
+/- Var	86.0%	66.7%	44.9%	50.8%	86.0%	56.2%
	A Market		Avg I	ocates per	· Day	203



Year-to-Date: 2017 Stats Compared with 2016

			Type T	'icket		
Pender	3 HR	CNCL	NEW	RXMT	UPDT	Total Tickets
2016	29	55	4480	59	793	5416
2017	109	89	6397	174	2904	9673
+/- Var	275.9%	61.8%	42.8%	194.9%	266.2%	78.6%
			Avg L	ocates per	c Day	77

## County Ticket Distribution



County/Place	06 Jun
NEW HANOVER	4212
BAYSHORE	13
CAROLINA BEACH	178
CASTLE HAYNE	108
FORT FISHER	2
KINGS GRANT	2
KIRKLAND	3
KURE BEACH	79
MASONBORO	4
MURRAYSVILLE	22
MYRTLE GROVE	46
OGDEN	59
SEA BREEZE	1

SEAGATE	2
SILVER LAKE	7
WILMINGTON	3622
WILMINGTON BEACH	1
WRIGHTSBORO	31
WRIGHTSVILLE	1
WRIGHTSVILLE BEACH	31

## County Ticket Distribution



County/Place	06 Jun
BRUNSWICK	5303
ASH	23
BALD HEAD ISLAND	31
BELVILLE	16
BOILING SPRING LAKES	28
BOLIVIA	110
CALABASH	270
CAROLINA SHORES	27
CASWELL BEACH	8
HICKMANS CROSSROADS	1
HOLDEN BEACH	43
LELAND	2852
LONG BEACH	2
LONGWOOD	6
NAVASSA	27
NORTHWEST	9

OAK ISLAND	364
OCEAN ISLE BEACH	192
SAINT JAMES	458
SANDY CREEK	1
SEA TRAIL PLANTATION	1
SEASIDE	1
SHALLOTTE	143
SHELL POINT	3
SOUTHPORT	379
SUNSET BEACH	95
SUNSET HARBOR	6
SUPPLY	179
TOWN CREEK	$\overline{}$
VARNAMTOWN	3
WINNABOW	21
1	

# County Ticket Distribution



County/Place	06 Jun
PENDER	1710
ATKINSON	5
BURGAW	235
CURRIE	165
HAMPSTEAD	633
MAPLE HILL	1
PENDERLEA	4
ROCKY POINT	476
SAINT HELENA	1
SCOTTS HILL	11
SLOOP POINT	7

SURF CITY	101
TOPSAIL	22
TOPSAIL BEACH	13
WALLACE	3
WATHA	9
WATTS LANDING	4
WILLARD	20

## **Events, Meetings, Holidays**





### **Upcoming Holiday**

Labor Day Monday, Sept. 4

All holidays are excluded from the three working day notice.

### **Board Meeting**

3Q17

October 19-20 Double Tree by Hilton Hotel New Bern River Front New Bern, NC

## NC Underground Damage Prevention Review Board Meetings

Located at: 2550 Operations Way, Raleigh, NC.
On the corner of Operations Way and Westinghouse Blvd.

October 17, 2017 10am to 4pm

### **State UCC Meetings**

PSNC Energy
Tue, Sept. 12, 2017
10am – 12pm
1801 Trinity Church Rd.,
Concord, NC 28027

**August 11, 2017** 



## Save the Date



ncpipesplus.org/mock-line-strike.html

### September 13<sup>th</sup> 2017

NC State Fairgrounds & Kerr Scott Building 1025 Blue Ridge Rd, Raleigh, NC 27607



### How can an 811 liaison help you today?







### Get a PDF copy of this presentation at www.ncucc.org

Use the UCC Issues form to voice your concerns to both local and state level UCC meetings in North Carolina. Available on both the NCUCC website and the NC811 app.

